

D I E S E L M O T O R C O A C H

D I E S E L M O T O R C O A C H



Dutch Star





Show Up in Style

The 2022 Dutch Star diesel motor coach sits perfectly at the center of your trip. From the start, safety is a priority with innovations like Comfort Drive™ steering technology, electronic stability control, tire pressure monitoring, and automatic traction control all equipped standard. You can upgrade your arrival with OnGuard™ collision mitigation technology with adaptive cruise control. The Dutch Star comes in 11 floor plans, with 37', 40', and 43' coaches—plus a choice between a Freightliner® or an optional Spartan® chassis.





Boutique Accommodations

From the full-paint Masterpiece Finish™—an industry exclusive—outside, to the stylish, functional, and thoughtful details throughout, the Dutch Star is a classic. For added safety, you'll find a keyless entry door with a touch pad and doorbell. Outside, large storage spaces—with upgradeable pass-through storage trays—mean plenty of space for storing your baggage.

Bahama full-paint Masterpiece Finish™

2022 DUTCH STAR

Awaiting Your Arrival

Enjoy your drive in the Dutch Star, with six-way power captain's chairs covered in Ultrafabric®, and coming with power lumbar, recliner, and footrests—and upgrade to optional heated seats. While you're cruising, side-view cameras show you everything around you on the rearview monitor screen, or opt for the 360-degree camera system. You can plan a perfect trip thanks to the new 9" Xite dash monitor with Nav-N-Go navigation system, which uses your coach's dimensions to create your route.



*Floor plan 4369 with Bahama décor
and Sable cabinetry*



Curated Comfort

The 2022 Dutch Star comes with several configurations that let you match your lifestyle. Choose dual recliners and a Trifold sofa, or any number of other options. You can enjoy the Samsung® 50" 4K LED TV and Bose® soundbar. Let the weather bring what it may, because you'll stay comfortable with standard porcelain tile floor and optional radiant heat and Penguin™ heat pump air conditioners. In rear-bath floor plans, you'll enjoy additional headroom from cathedral ceilings. And you'll stay connected anywhere with optional Wi-Fi connectivity.



World-Class Kitchen

In the galley of the 2022 Dutch Star, you'll find all of the meal-time amenities you'd want. High-gloss hardwood cabinetry with soft-close drawers and super-polished solid surface countertops are clean and sleek. A Whirlpool® refrigerator, stainless steel microwave, and three-burner cooktop are standard. You can upgrade your kitchen with a dishwasher and portable induction cooktop as well. An optional window allows more natural light inside, while the spacious pantry keeps the kitchen tidy.





A Sound Sleep

Inside the Dutch Star's master bedroom, you'll find a quiet haven to catch some rest. A pillow top mattress is available in king or queen size depending on your floor plan, and is upgradeable to a Sleep Number® mattress. Sitting opposite are a six drawer dresser and two large hanging cabinets, flanking a Samsung® LED TV.



Warm and Inviting

Depending on your floor plan, several shower options welcome you. One option is a spacious 50" x 34" version with mosaic inserts, a fold-down seat, glass door, and Aqua Miser® shower system. In the vanity, his-and-hers sinks offer plenty of space for getting ready. A multitude of storage options leave space for all of your other toiletries. Add an optional two-piece washer and dryer for laundry day. Many Dutch Star models also feature a mid-ship bathroom, which is perfect for you and guests alike.





Inside Out

Outside the Dutch Star, you'll find every bit as much luxury as inside. A Girard® G2000 power side awning—and the option to add a door-side awning or upgrade to a complete Nova awning package—you'll enjoy plenty of shade. A keyless entry door with touchpad and doorbell let you keep the outdoors at bay. Meanwhile, a Dometic® freezer on a pull-out tray is an available option—and you can upgrade to an entire outdoor entertainment center with a Samsung® 43" 4K LED TV and soundbar. All of which is powered by a standard Cummins Onan® diesel generator.

EXTERIORS



BAHAMA EXTERIOR

Awning Color: Linen Tweed



FULTON EXTERIOR

Awning Color: Charcoal Tweed



MIRAGE EXTERIOR

Awning Color: Charcoal Tweed



WYLIE EXTERIOR


Awning Color: Charcoal Tweed

INTERIOR DÉCOR



BAHAMA INTERIOR

a. Furniture/Fabric b. Flooring c. Counter Top




FULTON INTERIOR

a. Furniture/Fabric b. Flooring c. Counter Top




MIRAGE INTERIOR

a. Furniture/Fabric b. Flooring c. Counter Top



WYLIE INTERIOR


a. Furniture/Fabric b. Flooring c. Counter Top



*Available in High Gloss or Matte Finish


DUTCH STAR FLOOR PLANS

Length: 37' 11"




3709	Length	37' 11"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu

Length: 37' 11"




3717	Length	37' 11"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu

Length: 37' 11"



3736	Length	37' 11"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu


Length: 40' 09"



4020	Length	37' 11"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu


DUTCH STAR FLOOR PLANS

Length: 40' 09"




4081	Length	40' 09"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu

Length: 43' 09"




4310	Length	43' 09"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	85,000 btu

Length: 43' 09"



4311	Length	43' 09"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu


Length: 43' 09"



4326	Length	43' 09"	Grey Tank	75 gal.
	Width	101.5"	Sewage Tank	55 gal.
	App. Overall Height	13' 01"	Water Tank	105 gal.
	Interior Width	95.5"	Propane Tank	22 gal.
	Interior Height	83"	Furnace	50,000 btu

DUTCH STAR FLOOR PLANS


Length: 43' 09"



4328

Length	43' 09"	Grey Tank	75 gal.
Width	101.5"	Sewage Tank	55 gal.
App. Overall Height	13' 01"	Water Tank	105 gal.
Interior Width	95.5"	Propane Tank	22 gal.
Interior Height	83"	Furnace	50,000 btu


Length: 43' 09"



4363

Length	43' 09"	Grey Tank	75 gal.
Width	101.5"	Sewage Tank	55 gal.
App. Overall Height	13' 01"	Water Tank	105 gal.
Interior Width	95.5"	Propane Tank	22 gal.
Interior Height	83"	Furnace	50,000 btu

Length: 43' 09"



4369

Length	43' 09"	Grey Tank	75 gal.
Width	101.5"	Sewage Tank	55 gal.
App. Overall Height	13' 01"	Water Tank	105 gal.
Interior Width	95.5"	Propane Tank	22 gal.
Interior Height	83"	Furnace	50,000 btu






QUALITY YOU CAN FEEL

Like a fine home, the 2022 Dutch Star is framed 16 inches on center, and is covered by a fiberglass roof with walkable decking and an integrated gutter rail.

BASEMENT

Cargo Liner
3/8" Floor Decking
1 1/4" Bead Foam
Galvanized Sheeting (Prevents Distortion)



FREIGHTLINER											
FLOOR PLAN	ENGINE HP	AXLE RATIO	FUEL CAP.	WHEEL BASE	FRONT GAWR	REAR GAWR	TAG GAWR	GVWR	GCWR	APP. UVW	APP. NCC
3709	450	4.78	100 gal.	242	16000 lb.	24000 lb.	n/a	40000 lb.	50000 lb.	33900 lb.	6100 lb.
3717	450	4.78	100 gal.	242	16000 lb.	24000 lb.	n/a	40000 lb.	50000 lb.	33600 lb.	6400 lb.
3736	450	4.78	100 gal.	242	16000 lb.	24000 lb.	n/a	40000 lb.	50000 lb.	34200 lb.	5800 lb.
4020	450	4.78	100 gal.	252+TAG	17000 lb.	20000 lb.	12000 lb.	49000 lb.	64000 lb.	37700 lb.	11300 lb.
4081	450	4.78	100 gal.	252+TAG	17000 lb.	20000 lb.	12000 lb.	49000 lb.	64000 lb.	37400 lb.	11600 lb.
4310	450	4.78	150 gal.	288+TAG	19000 lb.	20000 lb.	12000 lb.	51000 lb.	66000 lb.	40100 lb.	10900 lb.
4311	450	4.78	150 gal.	288+TAG	19000 lb.	20000 lb.	12000 lb.	51000 lb.	66000 lb.	38100 lb.	12900 lb.
4326	450	4.78	150 gal.	288+TAG	19000 lb.	20000 lb.	12000 lb.	51000 lb.	66000 lb.	40000 lb.	11000 lb.
4328	450	4.78	150 gal.	288+TAG	19000 lb.	20000 lb.	12000 lb.	51000 lb.	66000 lb.	39100 lb.	11900 lb.
4363	450	4.78	150 gal.	288+TAG	19000 lb.	20000 lb.	12000 lb.	51000 lb.	66000 lb.	39900 lb.	11100 lb.
4369	450	4.78	150 gal.	288+TAG	19000 lb.	20000 lb.	12000 lb.	51000 lb.	66000 lb.	40000 lb.	11000 lb.

SPARTAN											
FLOOR PLAN	ENGINE HP	AXLE RATIO	FUEL CAP.	WHEEL BASE	FRONT GAWR	REAR GAWR	TAG GAWR	GVWR	GCWR	APP. UVW	APP. NCC
4020	450	4.88	100 gal.	252+TAG	17000 lb.	20000 lb.	12000 lb.	49000 lb.	64000 lb.	37900 lb.	11100 lb.
4081	450	4.88	100 gal.	252+TAG	17000 lb.	20000 lb.	12000 lb.	49000 lb.	64000 lb.	37600 lb.	11400 lb.
4310	450	4.88	150 gal.	288+TAG	20000 lb.	20000 lb.	12000 lb.	52000 lb.	67000 lb.	40500 lb.	11500 lb.
4311	450	4.88	150 gal.	288+TAG	20000 lb.	20000 lb.	12000 lb.	52000 lb.	67000 lb.	37800 lb.	14200 lb.
4326	450	4.88	150 gal.	288+TAG	20000 lb.	20000 lb.	12000 lb.	52000 lb.	67000 lb.	40000 lb.	12000 lb.
4328	450	4.88	150 gal.	288+TAG	20000 lb.	20000 lb.	12000 lb.	52000 lb.	67000 lb.	40000 lb.	12000 lb.
4363	450	4.88	150 gal.	288+TAG	20000 lb.	20000 lb.	12000 lb.	52000 lb.	67000 lb.	40300 lb.	11700 lb.
4369	450	4.88	150 gal.	288+TAG	20000 lb.	20000 lb.	12000 lb.	52000 lb.	67000 lb.	40100 lb.	11900 lb.

The content in our literature depicts and describes products that are subject to change. For the most recent images and information, please visit NewmarCorp.com.

Lengths, heights, widths, and dry weights are approximate. Weight will vary based on optional equipment added to the above base weight.

GAWR: Gross Axle Weight Rating is the maximum permissible weight for an axle.

GVWR: Gross Vehicle Weight Rating is the maximum permissible weight for a fully loaded motor coach.

GCWR: Gross Combination Weight Rating is the value specified by the manufacturer of the vehicle as the maximum allowable loaded weight of this motor coach and any towed trailer or towed vehicle.

UVW: Unloaded Vehicle Weight is the weight of this motor coach as built at the factory with full fuel, engine oil, and coolants. Does not include cargo, fresh water, propane gas, or dealer-installed accessories.

NCC: Net Carrying Capacity is the maximum weight of all occupants, including the driver, personal belongings, food, fresh water, waste water, propane gas, tools, tongue weight of towed vehicle, dealer-installed accessories, etc., that can be carried by the motor coach.

Specifications supplied by the chassis manufacturer.

Dutch Star R-Values:

Roof R-Value = 24

Sidewall R-Value = 11

Floor R-Value = 16

Basement R-Value = 4



EXTERIOR FEATURES

Full-Paint Masterpiece Finish™ with Clearcoat Finish and Diamond Shield Protection on Front Cap

Convex Chrome Exterior Mirrors with Defrost, Remote Control and Turn Signal Indicators

Chrome Power Baggage Door Locks, Keyless Entrance Door with Touch Pad and Door Bell

Entrance Door with Automatic Step

Assist Handle at Entrance Door

Rear Hitch for Towing Car

Mud Flaps

Rear Protective Tow Guard with Stainless Steel Newmar Name Cutout

Undercoating

Hydraulic Leveling Jacks

Stainless Steel Kick Panel at Entrance Door

Hammock Backer

Storage Bins in Pegboard Compartment

Wheelchair Lift*

OPTIONS

Patio Hammock Package-Specify 1 or 2

Baggage Door Stainless Steel Trim Kit

Flag Pole Bracket

Storage Tray 26" X 90" Power Location-Bay 2

Storage Tray 26" X 91" Non-Power Location-Bay 2

Storage Tray 32" X 91" Non-Power Location-Bay 2

Storage Tray 39" X 56" Non-Power Location-Bay 3

Storage Tray 42" X 91" Non-Power Location-Bay 3

Storage Tray 43" X 56" Non-Power Location-Bay 2

Storage Tray 43" X 56" Non-Power Location-Bay 3

Storage Tray 43" X 56" Non-Power Location-Bay 4

CONSTRUCTION FEATURES

Fiberglass Roof and Integrated Gutter Rail

Gelcoated Fiberglass Exterior Sidewalls, Front and Rear Caps

Aluminum-Frame Sidewalls and Roof Construction, 16" on Center

5/8" Foam Insulation Laminated in Sidewalls and Ceiling

Polar Pak R19 Batten Insulation on Roof

Automatic Lock Arms on Non Hydraulic Slideout Rooms-Paddle Style

Power Opening Entrance Door for Wheel Chair Lift on 4311

Egress Door with Ladder System

OPTIONS

Aire-Chair, Personal Chair Lift at Entrance Door

Dutch Star Dash



WINDOWS, AWNINGS, & VENTS

Frameless Double-Pane Tinted Safety-Glass Windows

Fan-Tastic® Vent with Rain Sensor in Kitchen and Bathroom

Hardwood Louvered Cover on Fan-Tastic® Vent in Kitchen

Skylight Above Shower*

One Piece Tinted Windshield

Driver Side Power Window

Carefree Slideout Covers and Power Entrance Door Awning with LED Lights

Girard® G2000 Power Side Awning with Wind Sensor, Remote Control and LED Lights

OPTIONS

Carefree Window Awning Package: 1-Bedroom, 1-Off Door Side Livingroom and 1-Door side Livingroom

Girard® Package: Two Nova Side Awnings, Slideout Covers, Entrance Door and Power Window Awnings

Additional Girard® G2000 Side Awning on Door Side

Bunk Windows*

Kitchen Window*

Two Nova Side Awnings

Screen Door Over Wheel Chair Lift Area on 4311

CHASSIS FEATURES

Freightliner® 450Hp on 37'

Freightliner® Tag Axle 450Hp on 40'-43'

Freightliner® V-Ride Drive Axle Suspension

Aluminum Wheels

Electronic Chassis Information Center in Dash

Cruise Control

Comfort Drive™ Steering with Power Column and Adjustable Control

Manual Tilt/Telescope Steering Wheel with VIP Smart Wheel

Recessed Fuel Fills with Crossover to Fill from Either Side

Back-Up Alarm

Anti-Lock Braking System

Chassis Battery Disconnect

Automatic Traction Control

Electronic Stability Control

Glass Dash Instrument Panel

Prep for OnGuard™ Collision Mitigation Adaptive Cruise System

Tire Pressures Monitoring On Non-Tag and Tag Axle Chassis

OPTIONS

Spartan® K2 Tag Axle 450Hp on 40'-43'

OnGuard™ Collision Mitigation Adaptive Cruise System with Adj. Following Distance Control on Freightliner® or Spartan® Chassis

AIR CONDITIONING & HEATING

Two 15M Penguin™ Heat Pump Air Conditioners on 37' and 40' Models

Three 15M Penguin™ Heat Pump Air Conditioners, Energy Management System, and 10KW Onan Generator on 43' Floor Plans

Chinook Dual Loop Heat with Continuous Hot Water

Dash Heater and Air Conditioner

Driver and Passenger Dash Overhead Ventilation System

Wall Mounted Sensors for Heating and Air Conditioning

Roof Air Conditioning Drainage System

OPTIONS

Electric Radiant Heat Installed Below Main Floor Tile

ELECTRICAL FEATURES

8.0 Kw Cummins Onan® Quiet Series Diesel Generator on Slide Out Tray

10.0 Kw Onan Generator on Slides 43'

50 Amp Electrical Service with Flexible Cord with Automatic Transfer Switch

Six 6-Volt House Batteries on Pullout Tray

Battery Disconnect Switch for House Battery

10 Watt Solar Panel to Charge Chassis Battery

12 Volt Auxiliary Receptacle on Dashboard

Emergency Engine Start Switch

Engine Block Heater

Energy Management System

Exterior Security Lights

Midship Side Turn Signals

LED Lights Recessed in Ceiling and Underneath Overhead Cabinets

Accent Lights in Slideout Fascia Trim

LED Lights in Pantry to Come on When Door is Open

Lights in Exterior Storage Compartments, Controlled by an Interior Master Switch

LED Lights Installed Under Door Side Slideouts

Manually Operated Hold-To-Run Slideout Switch

Automatic Generator Start on Low Battery or Temperature Setting

Cable TV Connection

Interior Courtesy Lights

Lights in Wardrobe



Reading Lights at Head of Bed-Dimmable with Adjustable Aim

USB Charger at Dinette and Bedroom Night Stand

USB Outlet at Dash for Driver Use

Power Rewind Wheel with 50' Cord*

KIB Backlight Switch Plates for Interior Lighting

KIB Switches for Interior Lights

Spare Fuses in the Chassis and House Fuse Panels

Wireless Phone Charger Pad in Driver Area

110 Volt Recept in Bed Overhead with Two Pass Through Ports

110 Volt/USB at Head of Each Bunk*

OPTIONS

Four Flexible 100 Watt Solar Panels on Roof

Recessed Docking Lights

Solar Prep Rated with 6 Gauge Wire Ran from Roof to House Battery Compartment

Transfer Switch with Surge Protector

PLUMBING & BATH FEATURES

Demand Water System

Sewage Holding-Tank Rinse

Dometic® China Bowl Stool or Macerator Stool*

Solid Surface Shower Walls with Mosaic Inserts and with Glass Door*

Fold Down Shower Seat

Water Filter for Entire Unit

Exterior Shower

Auto Fill Water Works Compartment

Power Water Hose Reel

Systems Monitor Panel

Aqua Miser® Shower System

OPTIONS

Assist Handle in Shower

Hot Water Line to Generator Area*

RV Sanicon Turbo System

INTERIOR FEATURES

Designer Feature Ceiling and Cathedral Ceiling with Added Height on Rear Bath Floor Plans*

Porcelain Tile Floor in Kitchen, Bathroom, Bedroom and Living Area

Interior Assist Handle at Main Entry Door

Power Stepwell Cover



Fitted Non-Quilted Bedspread with Accent Pillows
Decorative Wall Art
Hardwood Raised Panel Interior Passage Doors
Dash Panel Color Coordinated ABS
MCD Window Shades
MCD Power Shades at Windshield and Manual Shades at Driver and Passenger Side Windows
Waste Basket in Kitchen Base Under Sink
OPTIONS
Safe Located in Bedroom Wardrobe
MCD Power Window Shades with Remote Control
Shoe Storage Shelves Recessed into Rear Cap Wardrobe

CABINETS & FURNITURE

Bermuda Glazed Maple Hardwood Face Frame Cabinets with Mitered Raised Panel Doors with Matte Finish
Concealed Hinges on Cabinet Doors
Soft Close Cabinet Doors
Push To Release Drawer Slides in Pantry
Pullout Pantry Shelves with Travel Latch*
Drawers with Full Extension Ball Bearing Guides
Passenger Seat Work Station
Super Polished Solid Surface Countertop in Kitchen with Undermounted Stainless Steel Sink and Sink Covers
Super Polished Solid Surface Countertop in Bathroom and Bedroom
Ultrafabric on Front Seats
Front Seats Six Way Power, Power Lumber, Recliner and Footrest
Passenger Seat-Standard Width (Same as Driver Seat)
Villa Comfort Fit Furniture
Lifts on Bed Top
Plush Pillow Top Mattress
Dinette with Power Adjusted Table, Bench Seat and a Folding Chair on Wheelchair Accessible Floor Plan
Extended Rotation Concealed Hinge for Washer Dryer Cabinet Door
Appliance Garage in Kitchen*
Mesh Cell Phone Holder at Each Bunk Bed*
Molded Silverware Divider Tray
OPTIONS
Bermuda Glazed Maple Hardwood Cabinets with Mitered Raised Panel Doors-High Gloss
Toffee Glazed Maple Hardwood Cabinets with Mitered Raised Panel Doors-Matte or High Gloss Finish

Sable Maple Hardwood Cabinets with Mitered Raised Panel Doors-Matte or High Gloss Finish
Glacier Glazed Maple Hardwood Cabinets with Mitered Raised Panel Doors Matte or High Gloss Finish
Two Recliners with Lampstand and Reading Lights*
Two Recliners with Reading Lights*
Two Recliners, Lampstand, Reading Lights, Off Door Side with Hide-A-Bed Air Mattress and One Large Window
Two Ottomans*
Sleep Number® R5 Radius Corner Air Mattress
Buffet Dinette with Free Standing Table
Buffet Dinette, Two Fixed/Two Folding Chairs
Buffet Dinette, Two Fixed/Two Folding Chairs on 431l
Combination Desk with Buffet Dinette Table, Two Fixed/Two Folding Chairs
Combination Desk/Dinette with Free Standing Hidden Leaf Table, Two Fixed/Two Folding Chairs
Power Incline Retracting Bed Base with Sleep Number® R5 Air Mattress*
Queen Bed Layout
Queen Bed with Wardrobe and 62" X 36" Roll in Shower on 431l
Euro Booth Dinette with Two Table Leafs, Removable Table Leg and Two Folding Chairs
Powered Theater Seating 74**
Powered Theater Seating 87*
Heated Driver/Passenger Seats
Undermounted Double Bowl Solid Surface Kitchen Sink
Full Height Bed Base on 431l
Bunk Beds to Convert to Wardrobe

APPLIANCES & ACCESSORIES

Stainless Steel Convection Microwave with Three Burner Recessed Gas Cooktop
Air Horns
Whirlpool® 19.7 Cf. Stainless Steel Refrigerator with 2000 Watt Pure Sine Inverter
Prep for Two-Piece Washer/Dryer
Flush Gas Cooktop Cover of Matching Countertop Material
OPTIONS
30" Stainless Steel Convection Microwave in Kitchen Overhead on 431l
All Electric, Flush Mount Induction Cooktop, 8 AGM Batteries, and 2800 Watt Inverter
Dishwasher in Drawer with Stainless Steel Front
Central Vacuum Tool Kit
Dometic® 3.0 Cf. Freezer on Pullout Tray in Exterior Compartment
Electric Prep for Freezer (110 and 12 Volt) without Tray
Splendide® Two Piece Stacked Washer and Dryer



AUDIO, VIDEO & ACCESSORIES

Samsung® LED TV in Living and Bedroom Areas* (TV Sizes Vary Per Floor Plan)
Samsung® 50" 4K LED TV on Televator in Living Area*
Dash Radio with Harman/JBL 180 Watt Sound System and Subwoofer
Rearview Color Monitor System with Audio
Satellite Dish Prep on Roof
Two Bedroom Radio Speakers
TV Jack and 110 Volt Recept in Door Side Exterior Storage Compartment
Bluetooth Microphone for Dash Radio
Bose® Soundbar Sound System
High Definition Component Wiring
Side View Cameras Displayed onto Rear View Monitor Screen
10 Bc Fire Extinguisher, Smoke Detector, Propane and Carbon Monoxide Detector
Winegard Rayzar Automatic Digital TV Antenna
Xite Dash Radio with 9" Monitors and Nav-N-Go Navigation System
OPTIONS
Sirius® Satellite Radio Capability (Does Not Include Monthly Subscription)
Samsung® 43" 4K LED TV in Front Overhead
50" Televator with Fireplace in Place of Front Overhead TV on 431l
Exterior Entertainment Center in Sidewall with Samsung® 43" 4K LED TV with Bose® Soundbar
Exterior Entertainment Center in Storage Compartment with Samsung® 43" 4K LED TV with Bose® Soundbar
Omniview NS360 Camera System*
Prep for Ground Tripod Satellite Dish on Off Door Side with A/B Switch
Two-19" Skyworth TV/DVD Monitors at Each Bunk*
Universal Remote Control
Universal Toll Module
WiFi Ranger Denali/Spruce LTE
WiFi Ranger Tenton/Poplar Combo
Winegard Automatic Open Face SWM Satellite Dish-for DIRECTV STD/HD and In-Motion DIRECTV STD, DISH STD/HD
Winegard Automatic Dome Satellite Dish-for DISH STD/HD, DIRECTV STD and Bell Canada
Winegard Automatic Open Face Satellite Dish-for DISH HD and Bell HD TV
Winegard Automatic Open Face Satellite Dish and Winegard In-Motion for DISH Network
Winegard Automatic Open Face SWM Satellite Dish-for DIRECTV
Winegard In-Motion Dome Satellite Dish-for DISH STD/HD, DIRECTV STD. and Bell Canada

*Check with dealership on floor plan availability.

The content in our literature depicts and describes products that are subject to change. For the most recent images and information, please visit NewmarCorp.com.

The Newmar Customer Experience

The Newmar difference goes beyond our industry-leading motor coaches to provide you with an unrivaled ownership experience.



QUALITY FROM THE START

Every Newmar is crafted one at a time by folks who have spent an average of eight years building them. And each coach we assemble must undergo more than 1,000 tests and checks before ever leaving our factory.



FRIENDS FOR LIFE

Meet fellow owners through the Newmar Kountry Klub, a top social club for RV travelers that hosts rallies and other special events throughout the U.S. and Canada.



CAREFULLY SELECTED DEALERS

We view our dealership network in terms of quality, not quantity. Each of our dealers acts as a partner in our shared mission to exceed your highest of expectations, for an ownership experience that's second to none from day one.



SEAMLESS SERVICE

When you join the Newmar family, we pair you with a dedicated service specialist with expert knowledge of your exact coach. Available 24/7, our service specialists guarantee dealer warranty authorizations within four business hours and ship all in-stock parts the same day, free of charge.




EVERYTHING IN ONE PLACE

As a Newmar owner, you'll find resources specific to your coach through Newgle, an easy-to-use knowledge base that houses everything from user guides to technical support documents.



ROCK-SOLID PROTECTION

All models include a one-year/unlimited mileage limited warranty and a five-year, non-transferable structural warranty that covers your coach's superstructure in the event it fails to perform. Ask your Newmar dealer for more details.



A. ROOF

Fiberglass Roof

Batten Insulation

A/C Ducting

16" on Center Aluminum Rafter
Framing

Kraft Paper Vapor Barrier

5/8" Bead Foam

3/16" Panel

Padded Vinyl Overlay

B. SIDEWALL

Interior Wall Panel

5/8" Bead Foam

Kraft Paper Vapor Barrier

Batten Insulation

Composite One-Piece

Gelcoat Exterior Sidewall

Aluminum Framing

C. FLOOR

Tile

16" on Center Wood Framing

5/8" Floor Decking

Polyethylene Moisture Barrier

Batten Insulation

D. EXTERIOR

15M Penguin™ Heat Pump Central
Air Conditioners

One-Piece Bonded Windshield

Coated Aluminum Wheels

Frameless, Double-Pane,
Tinted Safety Glass Windows

Side-Hinged Baggage Doors with
Optional Pull-Out Tray

Our Partners

Newmar Quality Begins with the Company We Keep

You deserve class-leading performance from names you can trust. That's why we only work with suppliers dedicated to providing our customers with unrivaled quality, comfort, and support.

BASF

We create chemistry

The Coatings division of BASF is a global expert in the development and production of innovative and sustainable OEM and refinish coatings that deliver solutions beyond your imagination.



INDUSTRIAL FINISHES

Industrial Finishes has supported RV manufacturers for over four decades. The Industrial Finishes paint process delivers uncompromising quality, providing your coach with a true "Masterpiece" finish.



Driven By You

FREIGHTLINER CUSTOM CHASSIS

Freightliner Custom Chassis Corp. (FCCC) is renowned for delivering the industry's best ownership experience through exceptional 24/7 factory-direct support, exceptional ride and handling, and developing high-performance innovations such as DRIVETECH. It's the only RV driving system that prioritizes safety and automotive luxury by putting every command at your fingertips.



RIVERPARK

At RiverPark, we proudly represent the leading brands in consumer electronics—brands you know and trust to provide exceptional quality and innovative technology. Newmar features Samsung's incredible 4K TVs, Xite Infotainment systems featuring Rand McNally Navigation, Bose soundbars, and JBL and Infinity premium audio. Step into a 2022 Newmar and experience dazzling audio and video performance throughout the coach.



SPARTAN MOTORS

Spartan Motors is an American company with over 30 years of experience designing and manufacturing the premier motorhome chassis, which provides superior performance, exceptional safety ratings, and industry-leading technology.



When You Know the Difference.

Newmar Corporation | 355 N Delaware St | PO Box 30 | Nappanee, IN 46550-0030 | 574-773-7791 | Fax 574-773-2895

NewmarCorp.com